


Implementation of Low Damage Design



Three IL3 buildings – rocking walls, slotted beams & conventional wall/frames


A Snag...Testing of Supplemental Damping Devices

- Exterior Walls
 - Durability issues
 - Unable to add damping elements
 - Construction tolerances





Reinforcing Detailing

- Congestion in joints
 - very little tolerance
 - governed member sizes
- Location of bends
 - **Within column to prevent bursting**
- Casting of slot






Torsion Induced by Floor Rotation

- Asymmetric floor loading of beams
- Slotted beams have different mechanism to resist torsion
- Looked at torsion induced by orthogonal drift
- Pure pin gravity connection





Hysteretic Dampers



- Essentially short BRBs
- Low-cycle fatigue – calculation vs. scaled research vs. 1170.0 App B verification
- Adjustability on site

Damper Testing (HSL)

- Followed ACI374 loading protocol scaled to peak drift
- Failure due to inadequate embedment of core in restraining tube
- Addition of a steel bush achieved approx. 15x required fatigue life




Testing of Supplemental Damping Devices

- Prototype testing of full-scale devices (or as close as practicable) is a must if similar units have not been rigorously tested previously
- EN15129:2009 Anti-Seismic Devices (and similarly ACI 374) provides a logical and comprehensive approach to demonstrating performance
- The articulation and kinematic behaviour often associated to LDD systems removes many of the secondary load-paths that have provided stability in 'typical' systems
- It is important because devices do not necessarily scale from the lab to practice, particularly relative to end fixings which can be comparatively oversize at lab-scale and provide partial fixity at the ends
- Trying to incorporate details to accommodate 3D deformation of a joint region can result in significantly worse behaviour!


A Snag...Testing of Supplemental Damping Devices

- The prototype testing represents:
 - **Potential time delays – solved by accelerating that part of the design so that a specification for Tender can be sent-out ahead of time**
 - **Direct costs associated to fabrication of the prototype units and the testing**
 - **An opportunity to assure the client that they are getting a reliable and proven component that is fundamental to the structure performing well**
- Also furnishes key information for verification of building performance through modelling such as NLTHA often needed to demonstrate BC compliance



Reinforcing Detailing

- Note that an extension of the column is required above the slab level at top floor



Other points to check with Des

Things that make the design difficult

- Construction – getting the contractor to recognise the instability of the partially built structure (particularly before installation of dampers or stressing of PT)
- Secondary effects
 - beam torsion due to asymmetric floor loading
 - axial force in the beams due to diaphragm actions but limited/reduced connection to the column
 - Design for exterior exposure both architectural and durability of damping components such as BRF, friction interfaces (life-span and construction weathering)
- Supplemental Dampers
 - Designing for low-cycle fatigue vs. completing testing of a sufficient number of samples via Appendix B NZS1170.0 to demonstrate otherwise from calculation

Things that went well

- Contractor enthusiasm for a ‘special’ project generally overcomes perceived difficulties or unusual details/methodologies...just needs a lot of communication at kick-off
 - Presenting an example sequence of construction helps